



Phone: (573) 364-8659

FAX: (573) 364-8602

e-mail: dpryor@rollacity.gov

DEPARTMENT OF PUBLIC WORKS

901 North Elm

P.O. Box 979

Rolla, MO 65402

www.rollacity.gov

Date: _____

The City of Rolla is requesting a quote for patching RMU water main replacements and City sewer mains at various locations. The patch will consist of removing 4" of rock **and/or cold mix**, and placing 2 lifts of MoDOT approved compacted asphalt for a total of 4". Contractor will be responsible for all materials and labor for job. Contractor will have to produce vertical edge by means of cold milling a minimum of Six (6) feet wide. Patches requiring more or less than 4" of compacted asphalt will have an equitable adjustment made. City will provide water valve risers. All work orders will be issued with a Notice to Proceed and a Completion Date thirty (30) calendar days after the Notice to Proceed. If the contractor fails to complete the work order by the Completion Date a deduction of **\$100** will be made for each day that the work order remains incomplete after the completion date. The amount specified above is agreed upon, not as a penalty, but as liquidated damages for loss to the City of Rolla and the public. This amount will be deducted from any money due the contractor. The contractor will be liable for all liquidated damages. Permitting the contractor to continue the work after the expiration of the specified time or any extension of time will not constitute a waiver by the City of Rolla of any contractual rights. The time period for the quote is May 1st until December 1st. No work orders will be issued after November 1st. The City will provide traffic control signs. The Contractor **WILL BE RESPONSIBLE** for flagging and installing the signs for the patching. Asphalt must be installed with a paver. Crossings will not be required to be milled and laid with a paver. The quantities are estimated. The contractor will be responsible for all locates for water valves. Asphalt price will be indexed by converting the square foot to tonnage.

PROJECT: 614 – 2026 Asphalt Patching

| ITEM # | Description | Quantity | Unit | Unit Cost | Total |
|--------|----------------------|----------|------|-----------|-------|
| #1 | 4" Compacted Asphalt | 40,000 | SF | | |
| #2 | Mobilization | 6 | EA | | |

Deadline for Quote: April 22, 2026 11:00 a.m. **TOTAL** \$ _____

Signature: _____

Printed Name of Person Signing: _____

Company Name: _____

Company Address: _____

Phone: _____

FAX: _____

E-mail: _____